



10kW PV System BOM

Specification	Description	Quantity
500W PV module	PV PANELS	20
BDM-800	Dual Input Micro Inverter	10
BDG-256	Communication Gateway	1
LCF (Line Communications Filter)		option
Trunk cable drops	2m or 4m separate	10
Female Connector		2
AC interconnect cable	16 feet AC cable w/ female connector	2
End cap	male end cap w/female connector	2

Quantity:		Material:			
Designed by:	Checked by:	Approved by:	Date:	Edition:	Scale:
		Title: 10kW PV System(NA)			
Drawing number:				Sheet 1 of 1	