

Final Engineering Report

# Northern Electric Power Co.

MLRSD Testing

Report No.:R8271A-2

Date: 31 May 2022





## IMPORTANT NOTICE AND DISCLAIMER

1. This document is intended for the sole use of the Customer as detailed on the front page of this document to whom the document is addressed and who has entered into a written agreement with the PVEL entity issuing this document ("PVEL"). To the extent permitted by law, PVEL nor any group company (the "Group") assumes any responsibility whether in contract, tort including without limitation negligence, or otherwise howsoever, to third parties (being persons other than the Customer), and no company in the Group other than PVEL shall be liable for any loss or damage whatsoever suffered by virtue of any act, omission or default (whether arising by negligence or otherwise) by PVEL, the Group or any of its or their servants, subcontractors or agents. This document must be read in its entirety and is subject to any assumptions and qualifications expressed therein as well as in any other relevant communications in connection with it. This document may contain detailed technical data which is intended for use only by persons possessing requisite expertise in its subject matter.
2. This document is protected by copyright and may only be reproduced and circulated in accordance with the Document Classification and associated conditions stipulated or referred to in this document and/or in PVEL's written agreement with the Customer. No part of this document may be disclosed in any public offering memorandum, prospectus or stock exchange listing, circular or announcement without the express and prior written consent of PVEL. A Document Classification permitting the Customer to redistribute this document shall not thereby imply that PVEL have any liability to any recipient other than the Customer.
3. This document has been produced from information relating to dates and periods referred to in this document. This document does not imply that any information is not subject to change. Except and to the extent that checking or verification of information or data is expressly agreed within the written scope of its services, PVEL shall not be responsible in any way in connection with erroneous information or data provided to it by the Customer or any third party, or for the effects of any such erroneous information or data whether or not contained or referred to in this document.
4. Any energy forecasts estimates or predictions are subject to factors not all of which are within the scope of the probability and uncertainties contained or referred to in this document and nothing in this document guarantees any particular wind speed or energy output.

## KEY TO DOCUMENT CLASSIFICATION

Strictly Confidential	:	For disclosure only to named individuals within the Customer's organization.
Private and Confidential	:	For disclosure only to individuals directly concerned with the subject matter of the document within the Customer's organization.
Commercial in Confidence	:	Not to be disclosed outside the Customer's organization.
PVEL only	:	Not to be disclosed to non-PVEL staff.
Customer's Discretion	:	Distribution for information only at the discretion of the Customer (subject to the above Important Notice and Disclaimer and the terms of PVEL's written agreement with the Customer).
Published	:	Available for information only to the general public (subject to the above Important Notice and Disclaimer).



Project name:	MLRSD Testing	PVEL LLC
Report title:	Final Engineering Report	388 Devlin Road
Customer:	Northern Electric Power Co.	Napa, CA 94558
Customer Contact:	Ed Heacox	Tel: +1 415 320 7835
Date of issue:	31 May 2022	
Project No.:	8271	

---

**Task and objective:**

Assessment of the NEP PVG-2-L MLRSD to a powered thermal cycling test and a temperature verification of the RSD thermal shutdown function.

---


**Prepared by:**

**Verified by:**

**Approved by:**

Kevin Ly  
Test Engineer

Hazem Ajlani  
Project Manager

  
Kevin Gibson  
President

- 
- ☐ Strictly Confidential  
☐ Private and Confidential  
☐ Commercial in Confidence  
☐ PVEL Only  
☒ Customer's Discretion  
☐ Published

© PVEL, LLC. All rights reserved.

Reference to part of this report which may lead to misinterpretation is not permissible.

Revision	Date	Reason for Issue	Prepared by	Verified by	Approved by
1	April 27, 2022	Final	Kevin Ly	Hazem Ajlani	Todd Karin
2	May 31, 2022	Typo Correction	Kevin Ly	Hazem Ajlani	Kevin Gibson



# Table of contents

TABLE OF CONTENTS ..... 1

TABLE OF FIGURES..... 2

1 EXECUTIVE SUMMARY ..... 3

2 TEST PLAN OVERVIEW ..... 5

2.1 Test Population ..... 6

2.2 Powered Thermal Cycling ..... 7

2.3 Thermal Shutdown Validation ..... 8

2.4 Flame / Burn Test..... 9

3 TEST RESULTS ..... 10

3.1 Powered Thermal Cycling ..... 10

3.2 Thermal Shutdown Validation ..... 13

3.3 Flame / Burn Test..... 16

APPENDIX..... 17

ABOUT PVEL ..... 19



## Table of figures

Figure 1-1: Last 5 Days of TC200 .....	3
Figure 1-2: Thermal Shutdown Results.....	3
Figure 1-3: Flame / Burn Test in Progress .....	4
Figure 1-4: Post Flame / Burn Test .....	4
Figure 2-1: Test plan process diagram.....	5
Figure 2-2: NEP PV Guard RSD .....	6
Figure 2-3: NEP PV Guard RSD .....	6
Figure 2-4: DuT Setup.....	7
Figure 2-5: IEC 61215-2 2016 Thermal Cycling Profile.....	8
Figure 2-6: NEP PVG Datasheet .....	8
Figure 3-1: Thermal Cycling First 24 Hours .....	10
Figure 3-2: Thermal Cycling First 5 Days.....	11
Figure 3-3: Thermal Cycling Day 5 to Day 10 .....	11
Figure 3-4: Thermal Cycling Day 10 to Day 15 .....	12
Figure 3-5: Thermal Cycling Day 15 to Day 20 .....	12
Figure 3-6: Thermal Shutdown Temperature vs Voltage.....	13
Figure 3-7: Thermal Shutdown Temperature vs Current.....	14
Figure 3-8: Thermal Shutdown Temperature vs Power.....	14
Figure 3-9: Restart Operations Once Temperature Reaches Operating Range .....	15
Figure 3-10: Flame / Burn Test in Progress .....	16
Figure 3-11: RSD Enclosure Once Flame Source was Removed.....	16

# 1 Executive Summary

Northern Electric Power Co. (NEP) retained PVEL, LLC ("PVEL") to perform third-party independent performance and reliability qualification testing. This Final Engineering Report evaluates the NEP PVG-2-L module-level rapid shutdown device (MLRSD).

5 RSD devices were subjected to the powered thermal cycling test with 2 solar array simulators pushing PV power into each of the RSD. Throughout the 200 thermal cycles, the DuT remained operational throughout the test with no mis-operation nor derate.




Figure 1-1: Last 5 Days of TC200

The same 5 RSD devices were then subjected to a thermal shutdown validation by ramping up the temperature until the RSDs automatically shutdown. The first RSD began shutting down at 112.5°C and the last RSD shutdown at 117.5°C. Once the ambient temperature fell below the maximum operating temperature, the RSD's turned back on and the system continued to output power.




Figure 1-2: Thermal Shutdown Results



An RSD was subjected to a localized flame in order to observe the RSD's response to a flame. Throughout the test, the RSD remained operational even while the plastic enclosure of the RSD was melting.

Upon removal the of the flame source, the plastic enclosure quickly stopped burning.



**Figure 1-3: Flame / Burn Test in Progress**




**Figure 1-4: Post Flame / Burn Test**



## 2 Test Plan Overview

This report outlines the TC200 reliability test and thermal shutdown validation test performed on the NEP PVG-2-L MLRSD. The testing sequence aims to validate the MLRSD's performance over the reliability and validation tests to better understand operational advantages, while providing design feedback and supporting datasets on design and performance deficiencies.



**Figure 2-1: Test plan process diagram**

This evaluation focuses on a series of indoor (laboratory) tests to monitor the RSDs' capability to remain operational throughout the thermal cycling accelerated age testing profile as well as to validate the RSDs' ability to shut down upon an over temperature event. An explanation of each test is provided along with a description of the setup, equipment used to evaluate the results, and a short analysis of the inverter's performance.



## 2.1 Test Population

The NEP PVG-2-L PV device, presented in Figure 2-2 and Figure 2-3, is the module-level rapid shutdown device (RSD).




Figure 2-2: NEP PV Guard RSD



Figure 2-3: NEP PV Guard RSD



Table 2-1 details the testing population.

**Table 2-1 Test Population Summary**

Test DuT	Serial Number	Model Number
1	32110-110552d0-U	PVG-2-L
2	32110-11056AE0-U	PVG-2-L
3	32110-11055830-U	PVG-2-L
4	32110-11056E80-U	PVG-2-L
5	32110-11056900-U	PVG-2-L

## 2.2 Powered Thermal Cycling

During the powered thermal cycling test, each RSD is powered by 2 ETS80 solar array simulators (SAS) which feeds into the CPS inverter. Power is monitored from the ETS80 and at the string output.



**Figure 2-4: DuT Setup**



The thermal cycling test exposed the RSDs to rapid changes in environmental temperatures known to induce thermal cyclic fatigue on specific connections and components, including solder joints and PCBs. The temperature was cycled between -40 °C and 85 °C, as detailed in Figure 2-5, a total of two-hundred (200) times.




Figure 2-5: IEC 61215-2 2016 Thermal Cycling Profile

## 2.3 Thermal Shutdown Validation

The NEP PVG-2-L has a built in function that allows the RSD to shut down in the event of an over-temperature event. According to the datasheet below, the NEP PVG-2-L operating temperature range is between -40°C and 85°C.

Testing begins at the maximum operating temperature during normal operations and ramps up at 1°C per minute. Voltage, current, and temperature are continually measured to pinpoint the temperatures at which the RSDs' begin to open its relays and halt operations.

INPUT(DC)	Max DC Open Circuit Voltage per Input (Vdc)	90
	Max DC Current per input (Adc)	15
OUTPUT(DC)	Maximum Output Voltage (Vdc)	Voc * n (n=1/2/3/4)
SYSTEM	Maximum System Voltage (Vdc)	1500
MECHANICS	PV Cable	12AWG
	PV Connectors	Mc4 (Contact NEP for other connectors options)
	Size (not including PV cable)	5.12' x 4.73' x 1.14' (PVG-1) 5.90' x 5.71' x 1.00' (PVG- 2, PVG-3 ) 10.5' x 8.25' x 1.25' (PVG-4)
	Protection Degree	NEMA 6
	Operating Ambient Temperature	-40°C--+85°C
	Mounting Method	Rail, Frame (option)
SIGNAL	Communications	DC Power Line Compatible with SunSpec signaling
CERTIFICATION	Product Safety Compliance	UL 1741 CSA C22.2 No. 107.1 NEC 2014/2017 690.12 Canada CEC 2015 64-218

Figure 2-6: NEP PVG Datasheet



## 2.4 Flame / Burn Test

The flame / burn test is a quick safety test that characterizes the RSDs' response to fires. A butane torch applies high heat and flame to a localized point on the RSD to validate the RSDs' enclosure protection.

During the flame / burn test, the system is in normal operations.


## 3 Test Results

### 3.1 Powered Thermal Cycling

During the powered thermal cycling reliability test, the DuT are placed in an environmental chamber that can simulate high thermal stress environments.


Powered thermal cycling exposes the RSDs to a rapidly cycling temperature environment between  $-40^{\circ}\text{C}$  and  $85^{\circ}\text{C}$  while the DuT are operating. The temperature is cycled 10 times per day over 20 days. During this reliability test, voltage and current is logged to observe the RSDs' response to temperature cycling stress.

Over the 200 thermal cycles, the RSDs continued to output power with no sign of mis-operation. Refer to Figure 3-1 through Figure 3-4 for the thermal cycling temperature and power graphs.




**Figure 3-1: Thermal Cycling First 24 Hours**

\*Operational Note: During testing, 1 out of 5 RSD did not receive the full voltage and current throughout the test due to test equipment malfunction. Once the test equipment was resolved, the individual RSD returned to full operations for the remainder of the test. Data and graph represent the 4 out of 5 RSD that received the full voltage and current throughout the test. Dip in MPPT may be due to PVEL test equipment malfunction.




**Figure 3-2: Thermal Cycling First 5 Days**




**Figure 3-3: Thermal Cycling Day 5 to Day 10**

\*Operational Note: During testing, 1 out of 5 RSD did not receive the full voltage and current throughout the test due to test equipment malfunction. Once the test equipment was resolved, the individual RSD returned to full operations for the remainder of the test. Data and graph represent the 4 out of 5 RSD that received the full voltage and current throughout the test. Dip in MPPT may be due to PVEL test equipment malfunction.



**Figure 3-4: Thermal Cycling Day 10 to Day 15**



**Figure 3-5: Thermal Cycling Day 15 to Day 20**

\*Operational Note: During testing, 1 out of 5 RSD did not receive the full voltage and current throughout the test due to test equipment malfunction. Once the test equipment was resolved, the individual RSD returned to full operations for the remainder of the test. Data and graph represent the 4 out of 5 RSD that received the full voltage and current throughout the test. Dip in MPPT may be due to PVEL test equipment malfunction.




## 3.2 Thermal Shutdown Validation

Thermal Shutdown Validation tests the RSDs' ability to shutdown during an over-temperature event as well as its ability to restart once the temperature returns to its operating temperature range.


Testing begins during normal operations and at the maximum operating temperature of the DuT (85°C). The ambient temperature is increased at a rate of 1°C per minute until the RSDs shutdown.

Beginning at 112.50°C, individual RSDs began shutting down. Shown in Figure 3-6, the string voltage stepped down as each RSD opened their circuits. The final RSD shutdown at 117.54°C. Thermocouples are applied to RSDs using Kapton tape.




**Figure 3-6: Thermal Shutdown Temperature vs Voltage**





**Figure 3-7: Thermal Shutdown Temperature vs Current**




**Figure 3-8: Thermal Shutdown Temperature vs Power**



Once the thermal shutdown test concluded, the chamber doors were opened to allow the ambient temperature to gradually approach room temperature. As the RSDs cooled down, they returned to normal operations as the RSD temperature went below the maximum operating temperature (85°C).

The first RSDs began turning on at an average temperature of 81.99°C and the final RSD turned on at an average temperature of 75.44°C.



**Figure 3-9: Restart Operations Once Temperature Reaches Operating Range**

### 3.3 Flame / Burn Test

The flame / burn test is a quick safety test that characterizes the RSDs' response to fires. A butane torch applies high heat and flame to a localized point on the RSD to validate the RSDs' enclosure protection.

Throughout the test, the unit continued to operate while the plastic RSD enclosure was melting.

\*Operational Note: This Flame / Burn Test is a quick test which is not equivalent to a field fire



**Figure 3-10: Flame / Burn Test in Progress**

Upon removal of the flame, the unit did not continue to burn.



**Figure 3-11: RSD Enclosure Once Flame Source was Removed**



## Appendix

### NEP PVG-2-L Datasheet

INPUT(DC)	Max DC Open Circuit Voltage per Input (Vdc)	90
	Max DC Current per input (Adc)	15
OUTPUT(DC)	Maximum Output Voltage (Vdc)	$V_{oc} * n$ (n=1/2/3/4)
SYSTEM	Maximum System Voltage (Vdc)	1500
MECHANICS	PV Cable	12AWG
	PV Connectors	Mc4 (Contact NEP for other connectors options)
	Size (not including PV cable)	5.12' x 4.73' x 1.14' (PVG-1) 5.90' x 5.71' x 1.00' (PVG- 2, PVG-3 ) 10.5' x 8.25' x 1.25' (PVG-4)
	Protection Degree	NEMA 6
	Operating Ambient Temperature	-40°C---+85°C
	Mounting Method	Rail, Frame (option)
SIGNAL	Communications	DC Power Line Compatible with SunSpec signaling
CERTIFICATION	Product Safety Compliance	UL 1741 CSA C22.2 No. 107.1 NEC 2014/2017 690.12 Canada CEC 2015 64-218

## CPS Inverter Datasheet

Model Name	CPS SCA50KTL-DO/US-480	CPS SCA60KTL-DO/US-480
<b>DC Input</b>		
Max. PV Power	90kW (33kW per MPPT)	
Max. DC Input Voltage	1000Vdc	
Operating DC Input Voltage Range	200-950Vdc	
Start-up DC Input Voltage / Power	330V / 80W	
Number of MPP Trackers	3	
MPPT Voltage Range @ PF>0.99	480-850Vdc	540-850Vdc
Max. PV Short-Circuit Current (Isc x 1.25)	204A (68A per MPPT)	
Number of DC Inputs	15 inputs, 5 per MPPT	
DC Disconnection Type	Load-rated DC switch	
DC Surge Protection	Type II MOV, 2800V <sub>C</sub> , 20kA I <sub>TM</sub> (8/20 <sub>S</sub> )	
<b>AC Output</b>		
Rated AC Output Power @ PF>0.99 to ±0.91 <sup>1</sup>	50kW	60kW
Max. AC Apparent Power (Selectable)	50/55kVA	60/66kVA
Rated Output Voltage	480Vac	
Output Voltage Range <sup>2</sup>	422 - 528Vac	
Grid Connection Type	3Φ / PE / N (Neutral optional)	
Max. AC Output Current @480Vac	60.2/66.2A	72.2/79.4A
Rated Output Frequency	60Hz	
Output Frequency Range <sup>2</sup>	57 - 63Hz	
Power Factor	>0.99 (±0.8 adjustable)	
Current THD @ Rated Load	<3%	
Max. Fault Current Contribution (1 Cycle RMS)	64.1A (1.06/0.88 PU)	
Max. OCPD Rating	110A	125A
AC Disconnection Type	Load-break rated AC switch	
AC Surge Protection	Type II MOV, 1240V <sub>C</sub> , 15kA I <sub>TM</sub> (8/20 <sub>S</sub> )	
<b>System and Performance</b>		
Topology	Transformerless	
Max. Efficiency	98.8%	
CEC Efficiency	98.5%	
Stand-by / Night Consumption	<1W	
<b>Environment</b>		
Enclosure Protection Degree	NEMA Type 4X	
Cooling Method	Variable speed cooling fans	
Operating Temperature Range <sup>3</sup>	-22°F to +140°F / - 30°C to +60°C	
Non-Operating Temperature Range <sup>4</sup>	No low temp minimum to +158°F / +70°C maximum	
Operating Humidity	0 to 100%	
Operating Altitude	13,123.4ft / 4000m (derating from 9842.5ft / 3000m)	
Audible Noise	<60dBA @ 1m and 25°C	
<b>Display and Communication</b>		
User Interface and Display	LCD+LED	
Inverter Monitoring	SunSpec, Modbus RS485	
Site Level Monitoring	CPS FlexOM Gateway (1 per 32 inverters)	
Modbus Data Mapping	CPS	
Remote Diagnostics / FW Upgrade Functions	Standard / (with FlexOM Gateway)	
<b>Mechanical</b>		
Dimensions (HxWxD)	39.4 x 23.6 x 10.24in. (1000 x 600 x 260mm)	
Weight	Inverter: 123.5lbs/56kg; Wire-box: 33lbs/15kg	
Mounting / Installation Angle <sup>5</sup>	15 to 90 degrees from horizontal (vertical or angled)	
AC Termination	M8 Stud Type Terminal Block (Wire range: #6 - 3/0AWG CU/AL, Lugs not supplied)	
DC Termination <sup>6</sup>	Screw Clamp, Neg. Busbar (RSD version <sup>5</sup> ) Wire range: #14 - #6AWG CU	
Fused String Inputs (5 per MPPT) <sup>7</sup>	RSD <sup>6</sup> and Standard Wire-box: 20A fuses provided (Fuse values up to 30A acceptable)	
<b>Safety</b>		
Certifications and Standards	UL1741SA-2016, UL1699B, CSA-C22.2 NO.107.1-01, IEEE1547a-2014; FCC PART15	
Selectable Grid Standard	IEEE 1547a-2014, CA Rule 21, ISO-NE	
Smart-Grid Features	Volt-RideThru, Freq-RideThru, Ramp-Rate, Specified-PF, Volt-VAr, Freq-Watt, Volt-Watt	
<b>Warranty</b>		
Standard	10 years	
Extended Terms	15 and 20 years	



## About PVEL

PVEL is the leading reliability and performance testing lab for downstream solar project developers, financiers, and asset owners and operators around the world. With nearly ten years of experience and accumulated data, PVEL conducts testing that demonstrates solar technology bankability. Its trusted, independent reports replace assumptions about solar equipment performance with quantifiable metrics that enable efficient solar project financing and development. The PVEL network connects all major PV and storage manufacturers with 300+ global downstream partners representing 30+ gigawatts of buying power. PVEL's mission is to support the worldwide PV downstream buyer community by generating data that accelerates adoption of solar technology.